

Regional Office: Jorhat
Surendra Bhawan, 5th floor, Baruah Chariali, Jorhat, Assam-785001

ROJOR/OPRNS/MATRI/FUR/26-27

Date: 05.09.2026

TENDER DOCUMENTS FOR THE INTERIOR FURNISHING WORK FOR PROPOSED PREMISES OF MANTRIPUKHRI, MANIPUR STATE.

GENERAL TERMS AND CONDITIONS OF THE CONTRACT

ISSUE OF TENDERS FROM: 6 SEPTEMBER 2026 to 12 SEPTEMBER 2026.

LAST DATE OF SUBMISSION: 12 SEPTEMBER 2026 UPTO 3.00 PM HOURS.

TENDER OPENING DATE: 12 SEPTEMBER 2026, 3.30 PM HOURS.

(TENDERS WILL BE OPENED IN PRESENCE OF CONTRACTING AGENCIES)

PRICE OF THE TENDER DOCUMENT: NIL

EARNEST MONEY Rs.74595/- (Seventy four thousand five hundred and ninety five only) BY WAY OF PAY ORDER/Demand Draft FAVOURING UNION BANK OF INDIA PAYABLE AT JORHAT.

EXEMPTION: - EMD will be exempted on submission of valid proof documents for Micro and Small Enterprises (MSEs) as defined in MSE Procurement Policy issued by Department of Micro, Small and Medium Enterprises (MSME) or are registered with the Central Purchase organization or the concerned Ministry or Department

PLACE OF SUBMISSION:

UNION BANK OF INDIA, REGIONAL OFFICE
Surendra Bhawan, 5th floor, Baruah Chariali.
Jorhat, Assam-785001.

TENDER ISSUED TO: Empaneled Vendors Only. Tender form can be downloaded from official website of Union Bank of India e-tender page or through Govt Portal eprocure.gov.in.

Project Architect

M/s. Archtech
Flat No E2, Arun Enclave,
OM Path Opp- Sanskriti Gurukul School,
Ahom Gaon, Gorchuk Guwahati - 781035.
Ph: 7005205165

TENDER NOTICE

TENDER DOCUMENTS FOR THE INTERIOR FURNISHING WORK FOR PROPOSED PREMISES OF MANTRIPUKHRI, MANIPUR STATE.

1. Sealed item rate tenders are invited by **UNION BANK OF INDIA, REGIONAL OFFICE JORHAT Surendra Bhawan, 5th floor, Baruah Chariali, Jorhat, Assam-785001**. The approximate cost of the work is Rs. 14,91,890/-
2. The work to be completed within **04 weeks** from date of acceptance of work order placed by Union Bank of India. The work needs to be completed in a running Branch with restriction on removal of complete furniture and wiring.
3. The tenderers are required to complete form of tender, price the schedule of quantities and sign each page of tender documents before submission. The complete set is to be enclosed in a sealed envelope clearly specifying "TENDER DOCUMENTS FOR THE INTERIOR FURNISHING MODIFICATION WORK FOR NEW PREMISES OF MANTRIPUKHRI" along with Earnest Money of **Rs.74595/-** (Seventy four thousand five hundred and ninety five only) in the form of Pay Order / Demand Draft in favor of Union Bank of India, payable at Jorhat addressed to:

**ASSISTANT GENERAL MANAGER
Union Bank Of India
Surendra Bhawan, 5th floor, Baruah Chariali.
Jorhat, Assam-785001.**
4. Tenders will be received upto 3.00 PM on 12 SEPTEMBER 2026.
5. No tender will be received after the expiry of the time notified for receiving tenders under any circumstances whatsoever.
6. The tender will be opened at 3.30 PM on 12 SEPTEMBER 2026 at above address in the presence of authorized representative of contracting agency.
7. Tender shall remain valid for acceptance for a period of 90 days from the notified last date of tender submission.
8. The Bank reserves the right to reject any or all tender received without assignment of any reasons thereof.
9. The tender rate against each item of work / price indicated in the schedule of quantities and rates / price should be indicated both in words and figures. In case of any discrepancy, the rates indicated in words would prevail.
10. The rates quoted against each item of work / price should be for the complete finished item of work and include all labor, material, overhead, duties, etc but **excluding GST which should be quoted separately**. The Bank shall reimburse any statutory change in the tax structure after opening of the tender actual.
11. Each tender shall be accompanied by Earnest Money of **Rs.74595/-** (Seventy four thousand five hundred and ninety five only) in the form of Pay Order / Demand Draft in favor of Union Bank of India, payable at Jorhat. Tenders without Earnest Money shall be summarily rejected however EMD will be exempted on submission of valid proof documents for Micro and Small Enterprises (MSEs) as defined in MSE Procurement Policy

issued by Department of Micro, Small and Medium Enterprises (MSME) or are registered with the Central Purchase organization or the concerned Ministry or Department. The earnest money deposited shall not carry any interest and will be refunded to the unsuccessful tenderers. The Bank till completion of the work will retain earnest money paid by the successful contractor.

13. Earnest money paid by contractor shall be forfeited by the Bank if contractor fails to undertake the job if he is communicated about acceptance of his rates.

14. All tenders in which any of the prescribed conditions are not fulfilled or incomplete in any respect are liable to be rejected.

15. All contractors should obtain necessary insurance for their person deployed for working in the branch and Bank shall not be liable for any mishapening due to human error or accident.

16. This tender notice & empanelment letter shall form part of the contract documents.

APPENDIX TO THE CONTRACT DOCUMENTS

1. Defect liability period: 12 months from the date of virtual Completion of work.

2. Date of commencement: Within 7 days after the contract is accepted by the contractor

3. Date of completion: Four week from the date of acceptance of work order placed by Union Bank of India.

4. Liquidated damages: 5 % of contract amount per Week / day of delay subject to maximum of 40% of contract amount.

5. Period of honoring final certificate: 45 days

6. Value of work for interim certificate: NA

7. Period of honoring certificate: 15 days

8. Retention money: Retention Money of 5 per cent of the work order will be deducted from final bill and to be held with the bank for defect liability period(one year)and will be released only after completion of Defect liability period on vendors request.

9. Initial security deposit including: Rs.74595/- in the form of Earnest money deposit.

TENDER FOR INTERIOR FURNISHING WORKS OF UNION BANK MANTRIPUKHURI BRANCH, AT MANTRIPUKHURI, MANIPUR (UNDER R.O. JORHAT)					
I	INTERIOR WORKS				
NOTE:	The materials specified must be followed and in case of any deviation due to its unavailability, prior approval from Architect is a must.				
	Laminate (1.0mm thk) of Century/ Merino/ Greenlam/ NewMika, basic price-Rs.45/sft				
	THE RATES ARE EXCLUDING G.S.T. AND THE SAME SHALL BE PAID SEPERATELY.				
	All ply/ block boards to be used shall be of BWP and laminate fixing to be done with Revicol Marine.				
	(NOTE: IF DEVIATION IN THICKNESS OF LAMINATE IS FOUND, A DEDUCTION OF 30% OF THE QUOTED RATE SHALL BE MADE WITHOUT ANY CLARIFICATION)				
S.no.	DESCRIPTION	UNIT	RATE	QNTY	AMOUNT
1	TABLES (2'6" HEIGHT)				
	P/F tables of over all size of top as mentioned. It shall consist of 19mm thk. . ply on top and sides with suitable box type design in front and back part as per the detail drawings. The front side of the table shall consist of 19mm thick ply. 1Nos of drawer unit of size 16" (wide) fixed on telescopic channel and a shelf with shutter above 4" skirting to be provided with individual locks. The external surface of the table to be finished in 1.0 mm. Thk. Laminate (suede finish) of approved make and shade as per the Architects design; also the inner surface including drawer to be finished with with paint over wood primer and putty. Each top should be provided with 3" dia PVC wire manager of approved quality near the CPU / Monitor position. Rate shall also include the provision of locks of Godrej make or, equivalent 4" SS handles, CPU Trolley, Keyboard Tray in ply with laminate finish (1.0mm thick), foot				
I	OF SIZE: 6' LX 3' W (FOR BRANCH MANAGER)	NOS		1.0	
II	OF SIZE: 5' LX 2'6" W (FOR OFFICER)	NOS		0.0	
III	OF SIZE: 4'6L" X 2'9"W (FOR CONTINUOUS COUNTER)	RFT		25.0	
2	CASH COUNTER WITHOUT SIDE PARTITION & DOOR (5'6" X 7'0")	NOS		1.0	
	The overall height of the cash counter shall be 7'0" from floor finish level (ffl.). Providing and laying cash counter of over all size of top as mentioned or as per the drawing.. It shall consist of 19mm thk. . ply on top and sides with suitable box type design in facia with 14" transaction ledge facility on top at 3'10" ht. to be supported on the partition as per the detail drawings. The front side of the table shall consist of 19mm thick ply as per the design. 2Nos of drawer unit of size 16" (wide) fixed on telescopic channel and 1 no of shelf with shutter above 4" skirting to be provided with individual locks. The external surface of the table to be finished in 1.0 mm. Thk. Laminate (suede finish) of approved make and shade as per the standard design of the bank; also the inner surface to be finished with with paint over wood primer and putty. The facing edges of all ply wood sections should be either provided with steam beach lipping finished with melamine or edge tape. Each top should be provided with 3" dia PVC wire manager of approved quality near the CPU / Monitor position. Rate shall also include the provision of locks of Godrej make or, equivalent 4" SS handles, CPU Trolley, Keyboard Tray in ply with laminate finish (1.0mm thick), foot rest (finished with laminate), placing , fixing at site , transportation etc. complete. 12mm thick toughened Glass with frosted film paper and with proper provision of glass cuts for transaction and audibility of customers (as per design) to be provided/ fixed above the customer transaction top/ledge of				
3	FULL HT SOLID PARTITION IN LAMINATE FINISH (7' or above height)	SFT		209.0	
	P/F full height partition, the framing shall consist of aluminium square of size 50mm having wall thickness 1.20mm @ 600mm c/c both ways horizontally and vertically with necessary support from the RCC/ pucca ceiling. The framing shall be covered with 6 mm thk. ply on both side and finished with 1.00 mm thk. Laminate of approved shade. Rate shall be inclusive of necessary hardware items etc.				
4	FULL HT PARTLY GLAZED PARTITION (8' HT)	SFT		141.0	
	Specification same as above (full ht solid prtition) but with 6mm thick clear glass to be fixed above 3' till door height with teak wood patti as per design. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed. Rate shall be inclusive of all necessary hardware items, transportation etc.				
5	FULL HT PARTLY GLAZED SIDE PARTITION FOR CASH COUNTER (10MM THK TOUGHENED GLASS)	SFT		37.0	
	Specification same as above but with 10mm thick toughened glass to be fixed above 3' till door height/ with teak wood patti as per design and with proper provision of glass cuts for voucher/ receipt transaction. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed. Rate shall be inclusive of all necessary hardware items, transportation etc. complete.				

6	SEMI HT. SEMI GLAZED PARTITION	SFT	24.0
	P/F 4' height partition, the framing shall consist of aluminium square of size 50mm having wall thickness 1.20mm @ 600mm c/c both ways horizontally and vertically. The framing shall be covered with 6 mm thk. ply on both side and finished with 1.00 mm thk. Laminate of approved shade with 10mm thk approved make polished glass as per the drawing. Rate shall be inclusive of necessary hardware items, etc. Complete.		
7	SEMI HT. SOLID PARTITION IN LAMINATE	SFT	0.0
	Specification same as for FULL HT SOLID PARTITION above but of low ht as per the drawing. Rate shall be inclusive of necessary hardware items, etc. Complete.		
8	FULL HT FULLY GLAZED PARTITION WITH 12MM THICK TOUGHENED GLASS IN PATH FITTING FOR ENTRANCE (Make: Ebco/ Hardwyn or equivalent)	SFT	130.0
	P/F fully glazed frameless partition with 12mm thick toughened glass with necessary patch fittings & support from wall/ floor/ partition/ ceiling as per the site condition. The rate shall be inclusive of required wooden or aluminium support from ceiling at the same level of gypsum ceiling hardware items etc. Complete.		
9	GLAZED PARTITIONS OVER WORKSATATIONS	SFT	45.0
	P/F glazed partition as per approved design of 12mm thk clear glass mirror polished fixed with S S D Clips and grove made on Mullion Box/ partition as per design or as directed by the architect. Rate shall be inclusive of necessary ply support / mullion post (as per design) raised to support the structure hardware		
10	PANELLING ON COLUMN IN LAMINATE FINISH	SFT	380.0
	P/F panelling on wall/ column/ ceiling with framework of 18 gauge 50x50 mm Aluminium section framework at 600 mm c/c both way covered with 12mm ply and finished with 1.0 mm. thk. laminate of approved shade and make. Note: Architect's approval is required for panelling other than on columns in Banking Hall, without prior approval, no bill for the same shall be entertained.		
11	SINGLE SKIN PANELLING ON VANTILATORS (without covering material)	SFT	0.0
	P/F panelling on wall with 6mm thk. ply. The rate shall be inclusive of leveling the surface upto 2" (as per the site condition) from the existing wall/ column by using 19mm thk. ply framing.		
12	PANELLING/ PARTITION IN ONE SIDE ACP FINISH WITH DOOR & AC GRILL FOR AIR VENTILATION	SFT	200.0
	Providing and fixing partition in Aluminium Composite Panel (ACP) with framing of Aluminium Tube sections of min 1.5" x 1" and 20 gauge 2'-0" C/C both ways. Mirror screws to be used. Joints to be finished with Silicon based sealant. AC louvered grill of minimum size 6" x 2' x 2 nos to be used for air exhaust from back room of ATM. ACP thickness of 3 mm minimum of approved shade (SilverGrey or equivalent as per Bank's Layout policy). ACP to be in 2' width panels or distributed equally. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified brands to be used. Shades to be as per bank's approval. Trap door will be 12 mm marine		
13	SHUTTER BOXING IN ONE SIDE ACP FINISH	SFT	0.0
	Providing and fixing shutter boxing in Aluminium Composite Panel (ACP) with framing of Aluminium Tube sections of min 1.5" x 1" and 20 gauge 2'-0" C/C both ways. Mirror screws to be used. Joints to be finished with Silicon based sealant. ACP thickness of 3 mm minimum of approved shade (SilverGrey or equivalent as per Bank's Layout policy). ACP to be in 2' width panels or distributed equally. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified brands to be used. Shades to be as per bank's approval. Trap door will be 12 mm marine ply finished with ACP for rolling shutter wheel..		
14	MAIN ENTRANCE DOOR WITH 12MM THICK TOUGHENED GLASS IN PATH FITTING (Make: Ebco/ Hardwyn or equivalent) (FOR BANK & ATM)	SFT	45.5
	P/F single leaf fully Glazed frameless Door on Floor Spring (Weight Capacity upto 100 Kg) and Pivot with necessary fittings for the entrance door as per the manufacturer's specification. The Glass thickness should be 12 mm thk. Rate shall include floor springs, a pair of handles 18" SS Brushed finished etc with necessary hardware items.		
15	SOLID DOORS- IN LAMINATE FINISH (WITH OR WITH OUT VISION PANEL AS PER DIRECTION OF BANK / ARCHITECT) (Door closer make: EVERITE / HARDWIN / EVEREST/ equivalent)		
	Providing and fixing solid doors of sizes as shown in the drawing with 30mm solid flush door finished with 1.0 mm thick approved laminate on both sides. Rate shall include Mortise lock (Godrej Make), floor springs / door closure (as the case may be), door stopper, 5" hinges 4 Nos., buffers, etc with necessary hardware items and with / without door frames (frame size 4"x6" of 1st class sal wood) as mentioned		

I	WITHOUT DOOR FRAME (FOR UPS ROOM, BACK OFFICE ENTRANCE WITH DOOR CLOSER)	SFT		63	
II	WITH DOOR FRAME	SFT		0	
16	PARTLY GLAZED DOORS - WITH OUT FRAME	SFT		36.0	
	P/F doors of sizes as shown in the drawing. The door shutter shall be of 30mm thick flush door of approved make with for 6mm thk approved make clear float glass shall be provided at 3'0" from ffl. or as per the design with teak wood patti as per design. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed. The door shutter shall be finished in 1.0mm thk laminate on both sides. Rate shall include Mortise lock (Godrej Make), floor springs / door closure (as the case may be), door stopper, 5" hinges 4 Nos., buffers, etc with				
17	CASH COUNTER DOORS WITH NIGHT LATCH (MAKE: GODREJ/ DOORSET/ EQUIVALENT)	SFT		16.5	
	P/F solid doors of sizes as shown in the drawing. The door will be provided with Aluminium powder coated louvers of size 6"X18" above 12" from ffl. The doors are also to be provided with Godrej Night Latch. The door shutter shall be of 30mm thick flush door of approved make and finished with 1.0mm thick approved laminate on both sides. Rate shall include night latch, a pair of handles 5" SS Brushed finished 5" hinges 2 Nos. buffers tower bolts etc with necessary hardware				
18	LOW HIGHT DOORS	SFT		12.0	
	P/F solid doors of sizes as shown in the drawing. The door shutter shall be of 30mm thick flush door of approved make and finished with 1.0mm thick approved laminate on both sides. Rate shall include pair of handles 5" SS Brushed finished, 5" hinges 2 Nos. buffers tower bolts etc with necessary hardware items				
19	2'6" HT CONTINUOUS STORAGE(18" WIDE) (SIDE/ BACK STORAGE)	SFT		96.0	
	P/F low ht Storage unit of sizes as mentioned above. They shall consist of 19mm thk plywood for top, base and sides and back 6mm thk plywood, 19mm thk plywood shutter. The base of the storage to be raised 4" from ffl. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be made equally according to the length of the storage. A 19mm thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. All inner surfaces including shutters shall be finished with with paint over wood primer and putty. Rates shall be inclusive of all necessary approved fittings like hinges, locks, 3" long brushed finish handle, tower bolts and any other misc				
20	4'-0" HT CONTINUOUS STORAGE(18" WIDE) (BACK STORAGE)	SFT		0.0	
	P/F low ht Storage unit of sizes as mentioned above. They shall consist of 19mm thk plywood for top, base and sides and back 6mm thk plywood, 19mm thk plywood shutter. The base of the storage to be raised 4" from ffl. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be made equally according to the length of the storage. A 19mm thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. All inner surfaces including shutters shall be finished with with paint over wood primer and putty. Rates shall be inclusive of all necessary approved fittings like hinges, locks, 3" long brushed finish handle, tower bolts and any other misc				
21	8'-0" HT STORAGE WITH SHUTTER	SFT		172	
	Providing and fixing in position full Height Storage using 19mm thk plywood for top, base and sides and back 6mm thk plywood, 19mm thk plywood shutter. The base of the storage to be raised 4" from ffl. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be made equally according to the length of the storage. A 19mm thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. All inner surfaces including shutters shall be finished with paint over wood primer and putty. Rates shall be inclusive of all necessary approved fittings like hinges, locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved				
22	8'-0" HT STORAGE WITHOUT SHUTTER	SFT		0	
	Providing and fixing in position full Height Storage using 19mm thk plywood for top, base and sides and back 6mm thk plywood, 19mm thk plywood shutter. The base of the storage to be raised 4" from ffl. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be made equally according to the length of the storage. A 19mm thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. All inner surfaces including shutters shall be finished with paint over wood primer and putty. Rates shall be inclusive of all necessary approved fittings like hinges, locks, 3" long				

23	GYPSUM BOARD FALSE CEILING				
	P/F Gypsum Board False Ceiling straight or curve any profile of reputed make which includes G.I. Perimeter Channels of size 0.55mm thick (having One Flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling, screw fixed to brick wall / partition with the help of Nylon sleeves and screws at 610mm centres. Then suspending G.I. intermediate channels of size 45mm (0.9mm thick with two flanges of 15mm each) from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick fixed to soffit with G.I. cleat and steel expansion fasteners. Ceiling section of 0.55mm thick having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457 mm centres 12.5mm tapered edge Gypboard (conforming to IS 2095-1982) is then screw fixed to ceiling section with 25mm dry wall screws at 230mm centres. Screw fixing is done mechanically with drilling machine with suitable attachment. Finally tapered edges of the Gypsum boards are to be jointed and finished so as to have a flush look which includes filling and finishing with jointing compound, joint paper/fibre tape and two coats of dry wall top coat suitable for Gypsum board etc. complete as per the recommended practices / specifications of the manufacturer. Including making necessary				
I	FOR PLAIN AREA	SFT		322.0	
II	FOR CEILING DROP	RFT		180.0	
III	FOR TRAY LIGHT INCLUDING CEILING DROP	RFT		0.0	
24	FALSE CEILING	SFT		568.0	
	Mineral Fibre Acoustic Ceiling Tiles : Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong, Gyproc make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin-hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mm x 600mm x 15mm. with providing and fixing Hot dipped galvanised Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. The grid should be laid on Armstrong/Gyproc or equivalent stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 32 with 24 mm wide T - section flanges or of equivalent make, colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32 mm and 27mm ,25 mm respectively. The cost shall include all fittings and materials complete including proper installation and				
25	POP WORK (on existing putty)	SFT		1600.0	
	P/A one coat of Birla Wall Care Putty (Water resistant white cement based putty for concrete/ mortar walls and ceilings both internal and external) after removing all loosely adhering material from the wall surface with the help of emay stone, putty blade or wire brush and moisturing the wall with sufficient quantity of clean water as specified and directed by the department Thickness 1.00 mm				
26	PLASTIC EMULSION PAINT	SFT		3200.0	
	P/A plastic emulsion paint (base colour) on ceilings. The rates shall include scrapping, levelling & preparing the surface. Primer coat +(MINIMUM) 2 coats to get evenly spread quality finish(roller Finish) of approved make, quality and finish shall be provided. Note- Rates shall also include - filling up the cracks in the wall & ceilings making good surface				
27	ENAMEL PAINT ON ALL METAL WORKS	SFT		100.0	
	P/A 1 st quality oil paint of approved make, quality & shade. The rate shall include scrapping, levelling & preparing the surface with primer quote.				
28	ETCHING GLASS WITH FROSTED FILM PAPER (of approved design by the Architect)	SFT		220.0	
	Providing & Fixing frosted film fixed on the glass after cleaning and wiping glass surfaces free of any dust or foreign bodies and then fixed plain approved pattern / design film on the glass as per detail drawing inclusive of making necessary cutouts, carting away unserviceable materials out of compound, cleaning the site etc. complete as per the site requirements and the instructions of the Architect. (Basic Cost of Film not less than Rs 60/- Per SFT) (Measurement area = Length X Height)				
29	WRITING LEDGE 1'- 3" WIDE AS PER DESIGN	RFT		4.0	

	P/F wall/ column fixed writing LEDGE as per design. The top and sides of the table shall consist of 19mm thick ply and its back with 12mm thick ply as per the design. It should also have the provisions of open selves of size 6" on top for vouchers and slips. The exposed inner or outer faces should be finished with 1.0mm thick approved laminate				
30	BOXING FOR ROLLING SHUTTER	SFT		220.0	
	P/F boxing for rolling shutter with 19mm & 12mm ply. Necessary wooden framing shall be provided to support the structure with a openable shutter of 5" opening for smooth operation of shutters and rest is closed with mirror screws (for opening and servicing).. The boxing shall be finished on all exposed sides by 1.0mm thk laminate				
31	VERTICAL BLINDS WITH SCOTCH GUARD ONLY IN BANKING HALL	SFT		60.0	
	P/F in place 100 mm. Vertical blinds of approved make, quality and colour shade & pattern. Rate shall include necessary scotch guard treatment on both sides. The overlans should be uniform & adequate				
32	PIN-UP BOARDS / NOTICE BOARDS	SFT		12.0	
	P/F pinup or notice boards with hidden wall hanging provision. It consist 12mm thick soft boards of good density to be mounted over 12mm thick . ply as where required. The soft board will be covered with a plain fabric (appox Rs.250 /Rmts. of approved colour) from front and edges. Suitable border with 12mm thick plywood of size 2.5" to 3" to be fixed on all four sides and the same to be finished with 1.0mm thick laminate of approved shade				
33	CHEQUES DROP BOX (1' W X 10" D X 1.5' H)	NOS		1.0	
	P/F cheque drop box with hidden wall hanging provision made of 19mm thick board with slit opening of at the top of the box and an openable shutter with lock facility at the front side. All the exposed surfaces including all free edges are to be finished with 1 mm thick laminate of approved make and shade. Inner faces of board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer.Rate to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved design and quality.				
34	SUGGESTION BOX (1' W X 10" D X 1.5' H)	NOS		1.0	
	P/F suggestion box with wall hanging provision made of 19mm thick board with slit opening of at the top of the box and an openable shutter with lock facility at the front side. All the exposed surfaces including all free edges are to be finished with 1 mm thick laminate of approved make and shade. Inner faces of board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer.Rate to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved design and quality.				
TOTAL OF INTERIOR WORKS (WITHOUT GST)					