



Support Services Department, Union Bank Bhavan, 7th Floor,
239, Vidhan Bhavan Marg, Nariman Point, Mumbai – 400 021

QUOTATIONS FOR REPLACING WORN OUT FIBER SHED WITH METAL SHED FOR 500 KVA X 2 NOS & 320 KVA X 2 NOS. DIESEL GENERATING SETS IN DG YARD AREA AND PROVIDING NEW METAL SHED COVER FOR LIFT MACHINE ROOM, 150 TR CHILLER PLANTS & 165 TR CHILLER & PUMPS AT TECHNOLOGY CENTRE POWAI

REFERENCE QUOTATION NO. 007/2026

(ONLY FOR EMPANELLED CIVIL CONTRACTORS IN CLASS "D & E" – CLASS JOB UPTO Rs.15.00 LAKHS & Rs.5.00 LAKHS RESPECTIVELY IN MUMBAI/THANE REGION)



NOTICE INVITING SEALED QUOTATIONS
REFERENCE QUOTATION NO. 007/2026

To,
M/s _____

Dear Sir,

Sub: **QUOTATIONS FOR REPLACING WORN OUT FIBER SHED WITH METAL SHED FOR 500 KVA X 2 NOS & 320 KVA X 2 NOS. DIESEL GENERATING SETS IN DG YARD AREA AND PROVIDING NEW METAL SHED COVER FOR LIFT MACHINE ROOM, 150 TR CHILLER PLANTS & 165 TR CHILLER & PUMPS AT TECHNOLOGY CENTRE POWAI.**

(ONLY FOR EMPANELLED CIVIL CONTRACTORS IN CLASS "D & E" – CLASS JOB UPTO Rs.15.00 LAKHS & Rs.5.00 LAKHS RESPECTIVELY IN MUMBAI/THANE REGION)

Union Bank of India invites sealed quotations from Bank's Empanelled Civil Contractors in Class "D & E"- Class Job upto Rs.15.00 Lakhs & Rs.5.00 Lakhs respectively in Mumbai / Thane Region for undertaking the work at Technology Centre, Powai, Mumbai as per following details:

Name of the work : Quotations for replacing worn out fiber shed with metal shed for 500 KVA x 2 nos & 320 KVA x 2 nos. Diesel Generating sets in DG yard area and providing new metal shed cover for lift machine room, 150 TR Chiller plants & 165 TR Chiller & Pumps at Technology Centre Powai

Estimated Cost of the Work : Rs. 3,49,086/- plus applicable GST.

Earnest Money Deposit : Nil.

Period of Completion : 30 days

Validity of Quotation : 120 days

Date of Issue of Tender : Bid document can be downloaded from Bank's website www.unionbankofindia.bank.in from 10.00 am on 20-05-2026 till 1.00 pm on 08-06-2026.

Last date of submission of Quotation : Upto 15.00 p.m. on 09-06-2026

Date of Opening of Quotations : At 15.30 p.m on 09-06-2026

1) The Quotation document to be downloaded from Bank's website www.unionbankofindia.bank.in should be submitted in original, duly stamped, and sealed and drop in the **tender box kept at the following address: -**

SUPPORT SERVICES DEPARTMENT

SIGN & SEAL OF CONTRACTOR





**Union Bank of India,
Union Bank Bhavan,
239, Vidhan Bhavan Marg,
Ground Floor, Reception Area, Nariman Point,
Mumbai – 400 021.**

- 2) The item rates under the contract include complete supply of material and installation in all respects described in the bill of quantity. Contractor must quote item rates for all the items of work. Quotations will be opened in the presence of contracting agencies or their authorized representatives.
- 3) Quotations are to be submitted in one sealed envelope cover duly super scribed **“QUOTATIONS FOR REPLACING WORN OUT FIBRE SHED WITH METAL SHED FOR 500 KVA X 2 NOS & 320 KVA X 2 NOS. DIESEL GENERATING SETS IN DG YARD AREA AND PROVIDING NEW METAL SHED COVER FOR LIFT MACHINE ROOM, 150 TR CHILLER PLANTS & 165 TR CHILLER & PUMPS AT TECHNOLOGY CENTRE POWAI”**.
- 4) The tenderer must use only the quotation forms issued for the purpose to fill in the rates. Intimation of quote by any other means like letter, email will not be accepted.
- 5) Tenderers are advised not to make any alteration/modification in the document issued for the purpose, Item of work or in any respect whatsoever. Violation of this requirement will make the Quotation liable for rejection.
- 6) Every page of the quotation documents should be signed by the person or persons submitting the quotation in token of his/their having acquainted himself/themselves with the Conditions of Contract, Specifications etc., as laid down. Any tender with any of the documents not so signed will be subjected to rejection.
- 7) No consideration will be given to a quotation received after the time stipulated above and no extension will be allowed for submission of the tender. No quotations will be accepted by email or courier/speed posts etc.
- 8) The Union Bank of India shall not be bound to accept the lowest quotation and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.
- 9) This notice inviting quotation, the conditions and the duly completed form of quotation etc., will form part to be executed by the successful tenderer with the bank.
- 10) No advance payment will be made against the work. Final bill will be settled against completion of all the work as per BOQ to the satisfaction of the Bank.
- 11) All debris generated during the course of work has to be removed from the site by the appointed contractor.

SUPPORT SERVICES DEPARTMENT



For UNION BANK OF INDIA

ASST. GENERAL MANAGER

SIGN & SEAL OF CONTRACTOR

3

Support Services Department, Union Bank Bhavan, 7th Floor,
239, Vidhan Bhavan Marg, Nariman Point, Mumbai – 400 021

Sub: QUOTATIONS FOR REPLACING WORN OUT FIBER SHED WITH METAL SHED FOR 500 KVA X 2 NOS & 320 KVA X 2 NOS. DIESEL GENERATING SETS IN DG YARD AREA AND PROVIDING NEW METAL SHED COVER FOR LIFT MACHINE ROOM, 150 TR CHILLER PLANTS & 165 TR CHILLER & PUMPS AT TECHNOLOGY CENTRE POWAI.

(ONLY FOR EMPANELLED CIVIL CONTRACTORS IN CLASS "D & E" – CLASS JOB UPTO Rs.15.00 LAKHS & Rs.5.00 LAKHS RESPECTIVELY IN MUMBAI/THANE REGION)

BILL OF QUANTITY

a) 500 KVA x 2 Nos and 320 KVA x 2 Nos DG sheds					
Sr.No.	Description of Works	Qty	Unit	Rate	Amount
1.	Removing of old damaged fiber shed from top and providing & fixing roof sheet metal 0.5 mm thick make Jindal/ JSW / AN / NS profile blue/grey shed with necessary nuts/bolts/ screws etc.	2200.00	Sq.ft		
2.	Providing & Fixing of Aluminium metal box for water drainage system on the joints of metal sheets of size 12" x 4" both sides.	90.00	Rft		
3.	Providing Tarpaulin sheet 18' x 36"	648.00	Sq.ft		
				Total:	
				GST:	
b) Main building Terrace - Shed on Lift machine Room and vertical long frame with metal cover for stopping water on 150 TR chiller plant controllers.					
1.	Providing & fixing of roof top shed with Jindal/JSW/AN/NS profile metal blue/grey shed of 0.5 mm thickness.	450.00	Sq.ft		
2.	Providing & fixing 4" x 2" "I Section" bar with primer	100.00	Rft		

	red oxide coat & black paint finish.				
3.	Providing & fixing of 2" x 2" square pipe with red oxide primer & one coat of synthetic enameled paint.	120.00	Rft		
4.	Providing & fixing of 1" square metal pipe frame with red oxide primer & black synthetic enameled paint with blue /grey plain metal shed welded/screwed on frame to stop rainwater at terrace arc (chiller side) size : 20' x 3'	75.00	Sq.ft		
				Total:	
				GST:	
c) Hostel building Terrace - Shed on Controller of 165 TR Chiller Plants controller & pump panel, extension of shed on 1500 KVA DG set AMF panel and small shed on the entrance of main electrical panel room at hill side.					
1.	Providing & fixing of roof top shed with Jindal/JSW/AN/NS profile metal blue/grey shed of 0.5 mm thickness.	300.00	Sq.ft		
2.	Providing & fixing 4" x 2" "I Section" bar with primer red oxide coat & black paint finish.	50.00	Rft		
3.	Providing & fixing of 2" x 2" square pipe with red oxide primer & one coat of synthetic enameled paint.	50.00	Rft		
				Total:	
				GST:	

TOTAL [A+B+C]:Rs. _____ + GST @ _ = Rs. _____ = Rs. _____.

IN WORDS (in INR): _____.

ALTERATION: _____ / OMISSION: _____ / CORRECTIONS: _____

SUPPORT SERVICES DEPARTMENT

SIGN & SEAL OF CONTRACTOR



